Baystate Roads Program Local Technical Assistance Program (LTAP) **Tech Notes**



Tech Note #43

Pavement Preservation Checklist Series Thin Hot-Mix Asphalt Overlay Checklist

This checklist is one of a series created to guide State and local highway maintenance and inspection staff in the use of innovative pavement preventive maintenance processes. The series is provided through the joint efforts of the Pavement Preservation Program of the Federal Highway Administration and the Foundation for Pavement Preservation. To obtain other checklists or find out more about pavement preservation go to:

http://www.fp2.org http://www.fhwa.dot.gov/preservation/ http://www.fhwa.dot.gov/infrastructure/ asstmgmt/resource.htm

PRELIMINARY RESPONSIBLITIES

Project Review
☐ Is this project a good candidate for a thin hot-mix
overlay?
☐ What is the existing pavement sector?
☐ What is the average daily traffic and the percentage
of trucks and buses?
☐ Is rutting present? If so, is the rutting due to mix
instability?
☐ Is cracking present? If so, to what extent?
* Longitudinal
* Transverse
☐ Is the pavement structurally sound (no alligator
cracking or potholes)?
☐ Do other pavement distresses exist? If so, to what
extent:
* Raveling
* Polished aggregate
* Flushing/Bleeding
* Other



☐ Have drainage deficiencies been corrected?
☐ Review project for bid/plan quantities.
☐ Is this treatment cost-effective?

Document Review

- ☐ Bid specifications and special provisions
- $\ \ \Box \ Construction \ sequence$
- \square Mix design(s)
- $\hfill\Box$ Traffic control plan
- $\ \ \Box \ Construction \ manual$
- ☐ Material safety data sheets

Material Requirements

- ☐ Are materials from an approved source?
 - * Asphalt cement
 - *Aggregates(s)
 - * Tack coat
- ☐ Asphalt grade is based on environmental and traffic factors
- ☐ Aggregate(s) meet consensus and source properties.
- ☐ Aggregate(s) meet required polish (skid) value.
- \square Mix(es) are from an approved hot-mix plant.
- ☐ Mix(es) design, asphalt content, target gradation, and air voids meet specifications.

 □ Asphalt/aggregate mix has been checked for moisture susceptibility. □ Nominal maximum aggregated size is less than one third the overlay thickness for dense graded mixes. 	;-
PREOVERLAY INSPECTION RESPONSIBILITIES	
Equipment Inspections Cold Feed ☐ Aggregate stockpiles are clearly marked, separated and free of contamination. ☐ Aggregate cold feeds have been calibrated. ☐ All cold feed gates and belts are in working order.	
Asphalt Storage Tank ☐ Tank is capable of keeping the asphalt temperature within required specification range.	
Hot-Mix Plant ☐ The plant is properly calibrated and the scales have been checked. ☐ Production rates have been determined versus various aggregate moistures to provide a mix free of moisture. ☐ Temperature gauges and asphalt flow meter have been checked for accuracy. ☐ Mixing times have been established to assure the aggregate will be thoroughly coated with the asphalt cement. ☐ The plant is capable of providing the completed mix at the proper temperature within the required timeframe.	-
Surge/Storage Silo (if applicable) ☐ The maximum mix storage time has been established.	
Lime and Filler Silo (if applicable) ☐ The feeder system has been calibrated.	
Trucks ☐ Trucks are equipped (if required) with tarpaulins that meet State or local regulations.	
Tack Coat Distributor ☐ The distributor is properly calibrated.	

form tack coat at specified rate.

Paver


- ☐ Is a pick-up machine being used?
- ☐ Is a material transfer vehicle being used?
- ☐ Is the paving machine well maintained and in good working order?
 - * Tires are properly inflated or tracks properly adjusted
 - *Auger
 - * Screed
 - * Flow gates
 - * Slat conveyor
 - * Hopper wings


Rollers

- □ What type(s) of rollers will be used for breakdown, intermediate and finish rolling?
- ☐ A sufficient number of rollers of adequate size are available to achieve the desired compaction.
- ☐ Water spray bars, wetting pads, and scraping bars are working on all rollers to avoid material buildup.
- ☐ Steel drums are free of grooves and dents and not warped.
- □ Rubber tires (if applicable) are inflated to within +/-34.5 kPa (+/-5 psi).
- □ Vibratory plates or hand tampers are available for areas inaccessible to rollers.

Surface Preparation

- □ Pavement distress and drainage deficiencies have been corrected.
 - * Cracks greater than 7.9 mm (5/16") have been sealed within 3.2 mm (1/8") or flush with existing surface.





- * Alligator cracks and potholes have been removed and patched.
- ☐ Grade and cross-slope have been established.
- ☐ Manholes, catch basins, and utility appurtenances have been raised to level of new overlay.
- ☐ A scratch or leveling course, if required, is applied prior to the overlay.

PROJECT OPERATIONAL CONSIDERATIONS

Weather Requirements

- $\hfill \square$ Air/surface temperatures meet agency requirements.
- □ Paving does not begin if rain is imminent.
- ☐ Check temperature, wind, humidity, sun/clouds (and lift thickness). All will affect how quickly a mix cools and time available for compaction.

Traffic Control

- $\hfill\Box$ Signs and devices match the traffic control plan.
- ☐ The set-up complies with State/local agency requirements or the Federal MUTCD.
- □ Any unsafe conditions are reported to a supervisor.
- \Box The pavement will not be opened to traffic until it has cooled to 60°C (140 F) or the State's required temperature.

Surface Preparation

- \Box The surface is clean and dry.
- \Box The tack coat is being applied uniformly at proper rate.
- ☐ The tack coat is cured prior to placement of overlay.

Hot-Mix Plant

- ☐ Sample aggregate stockpiles and compare gradation of each to design.
- □ Sample aggregate from cold feeds and compare

- combined gradation to design.
- ☐ Sample aggregate to moisture and make any necessary adjustments to the hot-mix plant.
- ☐ Take random samples of aggregate per approved quality control plan.
- ☐ Sample hot-bin (if applicable) aggregates and run gradation, calculating percentage required from each bin to meet the design gradation.
- ☐ Check that asphalt cement is within the required specification range.
- ☐ Check plant mix for uncoated aggregate.
- ☐ Random sample and test plant mix, checking it against mix design:
 - * Temperature
 - * Percentage asphalt
 - * Gradation
 - * Air voids
 - * Other agency requirements

Trucks

- ☐ Sufficient trucks are available to allow the paver to keep moving a uniform speed.
- ☐ Trucks are clean and free of solvents before the mix is loaded.
- ☐ Trucks have tarpaulins to cover mix (when required).
- ☐ Trucks are insulated (when required).
- ☐ Trucks are loaded in a manner that avoids segregation.

Paving Machine

- □ Paving screed is preheated before starting placement.
- ☐ Mix arriving at the paving site is within the specified temperature range.



3 Tech Note #43 2006



- ☐ Mix is being placed at the proper grade and cross-slope at the specified thickness.
- \Box Surface texture is uniform, free of segregation, tearing or scuffing.
- □ Placement is providing a smooth riding surface.
- ☐ Automatic screed control is used whenever possible. (If manual controls are used, avoid frequent changes.)
- ☐ Construction joints (transverse and logitudinal) are tight with a smooth transition.
- $\hfill \square$ Quantity yields or thicknesses are checked throughout the placement.

Rollers

- ☐ A roller pattern has been established that achieves the proper in-place air voids.
- $\hfill\Box$ The established rolling pattern is being followed.
- ☐ Check density of finished mat:
 - are air voids within specifications?
- ☐ Steel-wheeled vibratory, steel-wheeled static, or rubber-tired rollers are used for breakdown and intermediate rolling.
- ☐ Steel-wheeled static rollers or vibratory rollers in the static mode are used for finish rolling.
- □ Vibratory rollers are operated--
 - * at an amplitude and frequency as selected according to mix harshness and lift thickness (for thin lifts, high frequency and low amplitude are usually used).
 - * at maximum frequency and a speed that provides a minimum of 1 impact per 2.54 cm (1").
 - * in the static mode when lift thekness is 2.54 cm (1") or less.
- □ Rubber-tired rollers--
 - * have tires warmed up to prevent pick-up.
 - * are used on scratch/leveling courses.

OPENING TO TRAFFIC

 \Box The pavement can be opened to traffic after the mix has been compacted and the mat has cooled to 60° C (140 F) or the agency's required temperature.

COMMON PROBLEMS AND SOLUTIONS (Problem: Solution)

- ☐ Plant mix discharge temperatures too low: Moisture in the stockpiles may be higher than initially planned; decrease production rate.
- □ Uncoated aggregate in the plant mix:
 - 1. Moisture may be in the aggregate.
 - 2. Worn or missing flights may be in the hotplant drum dryer.
 - 3. Mixing time may be too short (check slope of drum for drum mix plants).
- □ Segregation in the mix:
 - 1. Use multiple drops instead of a single drop when loading trucks from hot-mix plant storage silo.
 - 2. The haul truck should raise the truck bed slightly to break the load before unloading into the paver hopper.
 - 3. When the paver wings are folded, do it slowly and be sure mix remains above the flow gates.
 - 4. Keep a constant head of material to the paver's auger and screed.
 - 5. Harsher or stiffer mixes will require more care when placing and compacting.





- □ Lack of in-place density:
 - 1. The aggregate gradation may be outside of the target gradation.
 - 2. Asphalt content may be too low.
 - 3. Roller pattern or the frequency or amplitude of the vibratory roller may need adjusting.
 - 4. Plant mix may be below optimal rolling temperatures.
 - 5. Check the density of the underlying mat, which will influence nuclear gauge readings on thin overlays. If this is the case, a control strip can determine the maximum achievable density.
 - 6. Nominal maximum aggregate size may be too large to lift thickness. Use different mix or increase thickness.
- ☐ Plant mix has a lean or dull appearance:

 The mix may contain too little asphalt or an excess of minus No. 200 sieve material.
- ☐ Plant mix slumped in the haul truck:

 Properly mixed material in a haul truck will
 have a dome shape. If the load of mix has a flat
 shape, there may be excessive asphalt or moisture.
- ☐ Tears in the plant mix after rolling:

 Tearing of the surface occurs if the mix is too cold, too dry, has too many fines, has excess moisture, or has been overrolled.

- □ Poor surface smoothness or rough ride:
 - 1. Multiple stop-starts of the paver.
 - 2. Excessive paver speed.
 - 3. Improper use of manual screed controls.
 - 4. Vibratory rollers operating at excessive speed. (Impacts spaced too far apart).
 - 5. Poor joint construction practices.

SOURCES

Information in this checklist is based on or refers to the following sources:

Manual on Uniform Traffic Control Devices, Millenium Edition. 2000. Federal Highway Administration.

An Overview of Surface Rehabilitation Techniques for Asphalt Pavements. Pub. No. FHWA-PD-92-008. 1992. Federal Highway Administration.

Pavement Maintenance Effectiveness: Preventive Maintenance Treatments. Instructor's Guide, pp. 111-133. Pub. No. FHWA-SA-96-028, 1996. Federal Highway Administration.

Pavement Maintenance Effectiveness: Preventive Maintenance Treatments. Participant's Handbook, pp. 113-132. Pub. No. FHWA-SA-96-027, 1996. Federal Highway Administration.

Thin-Surfaced Pavements, Synthesis of User Practices. NCHRP Synthesis 260. 1998. Transportation Research Board, National Cooperative Highway Research Program.

5 Tech Note #43 2006